


INSTALLATION INSTRUCTIONS FOR SUTERA CS-2

FULLY IN-GROUND STEEL LID 2 cu.yd. CONTAINMENT CAPACITY FOR USED COOKING OILS





INSTALLATION INSTRUCTIONS

REQUIRED TOOLS, EQUIPMENT, MACHINERY:

- EXCAVATOR
- DUMP TRUCK
 - JUMPING JACK, PLATE COMPACTOR
- BUILDERS LEVEL
- STORY ROD
- HAND LEVEL (6ft.)

STEP No.1 - DETERMINE SITE LOCATION (SEE PG.2)

- a. NO OVERHEAD POWER LINES
- b. NO TREE OVERHANG
- c. NO CANOPY OVERHANG
- d. HAVE A SITE UTILITY LOCATE (UNDERGROUND) CONDUCTED WITHIN AREA OF PROPOSED INSTALLATION

LASER LEVEL

TAPE MEASURE

HAND SHOVEL

HAMMER DRILL

HAND RAKE

e. BE WITHIN REACH OF SERVICE CRANE TRUCK

STEP No.2 - EXCAVATION (SEE PG.3)

- a. TOP OF PRECAST TO BE 6.0" ABOVE FINISHED GRADE. PROVIDE A MIN. 3% GRADE SLOPING AWAY FROM UNIT.
- b. EXCAVATE TO THE REQUIRE WIDTH AND DEPTH.
- c. LEVEL AND COMPACT THE BASE OF EXCAVATION.
- d. APPROX. 2.0 cu.yds. OF MATERIAL TO BE REMOVED FROM SITE PER SUTERA CS-2.

STEP No.3 - INSTALLATION OF PRECAST CONCRETE (SEE PG.4)

- a. TAKE DELIVERY OF PRECAST UNIT WITH DELIVERY TRUCK CRANE, SITE CRANE OR EXCAVATOR, WHICHEVER IS AVAILABLE OR REQUIRED.
- b. USING SWIFT LIFT HOOK ANCHORS, 2 PER PRECAST UNIT, LIFT THE PRECAST MONOBASE AND SET INTO PLACE, ENSURE LEVEL, BOTH HORIZ. AND VERT.

LIFTING STRAPS FOR PRECAST CONCRETE AND STEEL LID

- C. ENSURE TOP OF PRECAST IS 6.0" ABOVE FINISHED GRADE, PROVIDE A MIN. 3% GRADE SLOPING AWAY FROM UNIT.
- d. DO NOT ALLOW DEBRIS OR WATER TO ENTER THE OPEN CONCRETE WELL, KEEP CLEAN AND DRY.

STEP No.4 - BACKFILL (SEE PG.5)

- a. Sutera units overall mass exceed the natural forces of hydrostatic pressure and will not float out of the ground, no extra measures are required to keep it in the ground.
- b. BACKFILL WITH NATIVE MATERIAL (EXCAVATED MATERIAL MAY BE USED IF SUITABLE).
- c. COMPACT IN SMALL LAYERS TO ACHIEVE 95% PROCTOR.
- f. DO NOT ALLOW DEBRIS OR WATER TO ENTER THE OPEN CONCRETE WELL, KEEP CLEAN AND DRY.

STEP No.5 - PLACING STEEL LID ON THE PRECAST WELL (SEE PG.6)

- a. LIFT THE STEEL LID WITH THE REQUIRED LIFTING STRAPS CONNECTED TO THE THREE (3) WELDED D-RINGS, WEIGHT OF STEEL LID IS 350 lbs (159 kg).
- b. LOWER ONTO PRECAST CONCRETE WELL, TAKING CAUTION NOT TO BEND THE FOUR (4) FASTENING TABS.
- c. ALIGN THE ACCESS LID TO THE REQUIRED POSITION.

STEP No.6 - FASTENING STEEL LID TO PRECAST CONCRETE WELL

- a. USING THE FOUR (4) STEEL FASTENING TABS AS A GUIDE, DRILL 0.5" DIA. HOLES 3.0" DEEP.
- c. INSTALL FOUR (4) 0.5" x 3.75" CONCRETE WEDGE ANCHORS AND TIGHTEN.

INSTALLATION IS NOW COMPLETE




INSTALLATION INSTRUCTIONS

CS-2

NOTE: ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED

pg. 1 of 7

DETERMINE SITE LOCATION



STEP No.1



INSTALLATION INSTRUCTIONS

CS-2


STEP No.1 - DETERMINE SITE LOCATION

- a. NO OVERHEAD POWER LINES
- b. NO TREE OVERHANG
- c. NO CANOPY OVERHANG
- d. HAVE A SITE UTILITY LOCATE
 (UNDERGROUND) CONDUCTED
 WITHIN AREA OF PROPOSED
 INSTALLATION
- e. BE WITHIN REACH OF SERVICE VACUUM TRUCK

NOTE: ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED

pg. 2 of 7

EXCAVATION



STEP No.2



INSTALLATION INSTRUCTIONS

CS-2


STEP No.2 - EXCAVATION


- a. TOP OF PRECAST TO BE 6.0" ABOVE FINISHED GRADE. PROVIDE A MIN. 3% GRADE SLOPING AWAY FROM UNIT.
- b. EXCAVATE TO THE REQUIRE WIDTH AND DEPTH.
- c. LEVEL AND COMPACT THE BASE OF EXCAVATION.
- d. APPROX. 2.0 cu.yds. OF MATERIAL TO BE REMOVED FROM SITE PER SUTERA CS-2.


NOTE: ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED

pg. 3 of 7

INSTALLATION OF PRECAST CONCRETE







STEP No.3



INSTALLATION INSTRUCTIONS

CS-2

STEP No.3 - INSTALLATION OF PRECAST CONCRETE

- a. TAKE DELIVERY OF PRECAST UNIT WITH DELIVERY TRUCK CRANE, SITE CRANE OR EXCAVATOR, WHICHEVER IS AVAILABLE OR REQUIRED.
- USING SWIFT LIFT HOOK ANCHORS, 2
 PER PRECAST UNIT, LIFT THE PRECAST
 MONOBASE AND SET INTO PLACE,
 ENSURE LEVEL, BOTH HORIZ. AND VERT.
- C. ENSURE TOP OF PRECAST IS 6.0" ABOVE FINISHED GRADE, PROVIDE A MIN. 3% GRADE SLOPING AWAY FROM UNIT.
- d. DO NOT ALLOW DEBRIS OR WATER TO ENTER THE OPEN CONCRETE WELL, KEEP CLEAN AND DRY.

NOTE: ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED

pg. 4 of 7

BACKFILL

STEP No.4




INSTALLATION INSTRUCTIONS

CS-2

STEP No.4 - BACKFILL

- a. SUTERA UNITS OVERALL MASS EXCEED
 THE NATURAL FORCES OF HYDROSTATIC
 PRESSURE AND WILL NOT FLOAT OUT OF
 THE GROUND, NO EXTRA MEASURES
 ARE REQUIRED TO KEEP IT IN THE
 GROUND.
- b. BACKFILL WITH NATIVE MATERIAL (EXCAVATED MATERIAL MAY BE USED IF SUITABLE).
- c. COMPACT IN SMALL LAYERS TO ACHIEVE 95% PROCTOR.
- d. DO NOT ALLOW DEBRIS OR WATER TO ENTER THE OPEN CONCRETE WELL, KEEP CLEAN AND DRY.




NOTE:
ALL DIMENSIONS ARE
IN INCHES UNLESS
OTHERWISE SPECIFIED

pg. 5 of 7

PLACING STEEL LID ON THE PRECAST CONCRETE WELL

STEP No.5





CS-2

STEP No.5 - PLACING STEEL LID ON THE PRECAST WELL


- a. LIFT THE STEEL LID WITH THE REQUIRED LIFTING STRAPS CONNECTED TO THE THREE (3) WELDED D-RINGS, WEIGHT OF STEEL LID IS 350 lbs (159 kg).
 b. LOWER ONTO PRECAST CONCRETE
- b. LOWER ONTO PRECAST CONCRETE
 WELL, TAKING CAUTION NOT TO BEND
 THE FOUR (4) FASTENING TABS.
- c. ALIGN THE ACCESS LID TO THE REQUIRED POSITION.

NOTE: ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED

pg. 6 of 7

FASTENING STEEL LID TO PRECAST CONCRETE WELL

STEP No.6





CS-2

STEP No.6 - FASTENING STEEL LID TO PRECAST CONCRETE WELL

- a. USING THE FOUR (4) STEEL FASTENING TABS AS A GUIDE, DRILL 0.5" DIA. HOLES 3.0" DEEP.
- c. INSTALL FOUR (4) 0.5" x 3.75" CONCRETE WEDGE ANCHORS AND TIGHTEN.

NOTE: ALL DIMENSIONS ARE IN INCHES UNLESS OTHERWISE SPECIFIED

pg. 7 of 7



ENSURE THE FOLLOWING IS DONE PRIOR TO COMPLETION:

- ENSURE ALL DEBRIS AND WASTE IS REMOVED CAUSED BY INSTALLATION.
- WIPE CLEAN ENTIRE UNIT WITH CLEAN RAG AND MILD DETERGENT.
- SPRAY ALL EXPOSED STEEL WITH KROWN RUST PROOFING & LUBRICANT. DO NOT WIPE OFF IMMEDIATELY, ALLOW TO PENETRATE FOR 24 HRS.
- SPRAY ALL MOVING COMPONENTS, KEY HOLE AND UNDERSIDE OF PUSH PAD ON SLAM LATCH ASSEMBLY WITH WHITE LITHIUM GREASE.

INSTALLATION IS COMPLETE